



Janice Phelps - Sample Estimate 123 Anystreet St.

Everywhere NV 99981

Submitted By:

Bravo6 Tile & Stone, LLC

671 Beckwourth Drive Reno NV 89506

Mobile: (775) 895-9024 bravo6tile@gmail.com

www.Facebook.com/Bravo6Tile Instagram:@Bravo6Tile NV C-20 Ceramic Tile & Stone License: 0090502

Licensed | Bonded | Insured

Bravo6 Tile & Stone, LLC

671 Beckwourth Drive Reno NV 89506

Mobile: (775) 895-9024 bravo6tile@gmail.com

www.Facebook.com/Bravo6Tile Instagram:@Bravo6Tile

NV C-20 Ceramic Tile & Stone License: 0090502

Licensed | Bonded | Insured



Estimate

Job Name Job Number Issue Date Valid Until Permit Number

Janice Phelps - Sample Estimate 0271 December 5, 2022 January 4, 2023 TM7891

Customer

Estimator

Kris Blanchard

Janice Phelps Sample Estimate 123 Anystreet St. Everywhere NV 99981

Mobile: 775-900-7214

bravo6tile@gmail.com

Mobile: 775-912-3478

janicephelps_sample@abc123.com

Description

SAMPLE ESTIMATE.

Installation of tile in the entry way, master bathroom floor, backsplash in the master bathroom, and the living room accent wall.

Measurements:

Breakdown of Tiles:

Special design notes:

Item Quantity Amount

Entry Way \$1,631.62

72"x102" entry way hall. 51 SF

Labor

UCM - Prep Horizontal surfaces

51 Ea

Labor Only - UCM - Prep work to prepare horizontal surface for proper tile installations, 1/8" deviation in 10 feet min, 1/16" in 6 ft / SF,

Cer/Porc Tile Mid Size Horizontal /SF

51 Ea

Labor Only - Installation of standard format ceramic or porcelain tile from 12"x12" up to 12"x24" on a horizontal surface over proper prep, cement grout by the SF

Estimate December 5, 2022

Item	Quantity	Amount
Materials		
Materials Total: \$644.61		
Schluter Ditra UCM 323 SF/Roll (3'3"x98'5")	1 each	
Laticrete LHT Grey 50 lbs	5 each	
Laticrete SpectraLock 1 #09 Frosty 1 Gal	1 each	

Master Bathroom \$4,368.32

146"x96" = 97.3 SF

Labor

UCM - Prep Horizontal surfaces

97.3 Ea

Labor Only - UCM - Prep work to prepare horizontal surface for proper tile installations, 1/8" deviation in 10 feet min, 1/16" in 6 ft / SF.

Cer/Porc Tile Mid Size Horizontal /SF

97.3 Ea

Labor Only - Installation of standard format ceramic or porcelain tile from 12"x12" up to 12"x24" on a horizontal surface over proper prep, cement grout by the SF

Disposal - Small Load

1 Ea

Small Load - Disposal of construction materials by the truck load, including transport, dump fees, and hand or mechanical unloading. Per trip.

Instal of Metal Trim/Transitions /LF

12 Ea

Labor Only - Metal Trim/transition installation, per Linear Foot

BS-Ceramic/Porcelain, 35 SF No Sealer

1 Ea

Backsplash package deal including demolition, disposal, prep, and installation of ceramic or porcelain mosaics or tiles less than 12" on any side, with cement grout - NO SEALER. No special edging, border details, or inlaid patterns, or metal included.

Materials

Materials Total: 370.38

Laticrete LHT Plus Grey 50 lbs 6 each
SILK Patch 10 lbs 2 each
Laticrete SpectraLock 1 #57 Hot Cocoa 1 Gal 2 each
Laticrete Unsanded Premium Acrylic Caulk #03 Silk 4 each

Accent Wall \$3,209.24

Living Room Accent Wall - 120"x96" = 80 SF

Labor

Caulking LF 36 Ea

Labor only installing acrylic/silicone caulking /LF

CBU Prep Walls 80 Ea

Labor Only - Prep vertical area with CBU (cement board).

Quantity **Item Amount** Cer/Porc Tile Mid Size Vertical /SF 80 Ea Labor Only - Installation of standard format ceramic or porcelain tile from 12"x12" up to 12"x24" on a vertical surface over proper prep, cement grout, by the SF **UG-Standard Area-High Performance Grout** 80 Ea Labor Only - Installation of upgrade/pre mixed/high performance/epoxy grout, per SF. **Materials** Materials Total: \$375.72 6 each CBP 7/16" WonderBoard LITE Cement Backerboard 3'x5' Laticrete Tri-LITE White 30 lbs 3 each 2 each Laticrete SpectraLock 1 #42 Platinum 1 Gal Laticrete Unsanded Premium Acrylic Caulk #87 Stormy Grey 4 each Fee's & Discounts \$0.00 **Veteran's Discount** 1 Ea \$500 discount applied to final invoice. Thank you for your service! Subtotal \$9,209.18 Tax \$337.52 \$9.546.70 **Price Draw Schedule** 100% Of Materials To Start \$1,390.71 50% Of Labor To Start \$4,078.00 50% Of Labor On Completion \$4,077.99 Final Invoice \$0.00 Date 12/5/22 Date

Janice Phelps

Sample Estimate

Kris Blanchard

Bravo6 Tile & Stone, LLC







